


Construction Schedule:

- The work on Main Street shall be done in phases. Only one block can be disturbed at one time. The previous block must be fully paved prior to removal of the next block. Only one intersection at a time can be closed. For instance, S. Pearl intersection must be opened back up for vehicular traffic and pedestrian traffic prior to closing the S. Second Street intersection.
- The Sanitary sewer section of S. 2nd Street can be closed at any time.
- Contractor is to maintain pedestrian traffic next to building. Contractor is to provide all safety requirements including fencing.
- Coordinate all work with the Owner and business owners along the project.
- The Contractor Shall maintain 2-way traffic on Main Street. This can be done using the center parking on Main Street. Provide Traffic Control as necessary. Keep one block of Main Street Parking available to the public at all times. This ensures patrons will not have to walk more than one block to a business along the construction areas.

Item No.	Description	No. of Units
1.	Mobilization	LS
2.	Traffic Control	LS
3.	Pavement Removal	3,406 SY
4.	Structural Fill	140 CY
5.	Core-Out	60 CY
6.	12" Portland Cement Treated Soil	700 SY
7.	6" PCC Sidewalk, 1.5" Styrofoam, & 12" Subgrade Prep	2,680 SF
8.	5" PCC Sidewalk w/ 12" Subgrade Prep	833 SF
9.	Stairs w/ 12" Subgrade Prep	887 SF
10.	Safety Hand Rails	55 LF
11.	Detectable Warning Panel	154 SF
12.	7" PCC w/ 12" Subgrade Prep	2,936 SY
13.	Storm Sewer Connection w/ Collar	1 EA
14.	18" Storm Sewer, Trenched	659 LF
15.	15" Storm Sewer, Trenched	139 LF
16.	12" Storm Sewer, Trenched	128 LF
17.	10" Storm Sewer, Trenched	30 LF
18.	15"x12" Tees	2 EA
19.	Drainage Manhole (SW-401) Base, Ring & Cover	2 EA
20.	48" Drainage Manhole (SW-401)	6.8 VF
21.	Intake, SW-501	1 EA
22.	Intake, SW-511	9 EA
23.	8" PVC Sanitary Sewer (SDR 26), Trenched	212 LF
24.	6" PVC Sanitary Sewer Service (SDR 23.5), Trenched	74 LF
25.	Service Wyes, 45s, Marker	4 EA
26.	Sanitary MH Base, Ring & Cover, Chimney Seal	2 EA
27.	48" Sanitary MH w/ Eccentric Cone	20.0 VF
28.	Utility Exploration for Depth	3 EA



True Engineering
land surveying llc
325 Howard Rd.-Meville, IA 51039
712.870.9789

No.	REVISIONS	DATE

2020 Main Street & S. 2nd Street
Improvement Project
Meville, Iowa

Overview of Project

JOB NO:

DATE:
2.05.2020

SHEET:

CX